

**STANDARD VERTICAL TUBE DAY GATE
LEVER HANDLE KEYED OUTSIDE
LEVER HANDLE THUMB LATCH INSIDE
ADA COMPLIANT**

CONSTRUCTION:

FRAME 1-1/2" X 1/2" ALUMINUM BAR
SOLID CENTER BAR 4" X 1-1/2" ALUM.
FINISH IS BRUSHED ALUMINUM
3/4" STAINLESS STEEL TUBE- BARS
HINGE - DOUBLE HINGE PIN DESIGN,
WITH BUSHINGS


OPTIONAL:

MECHANICAL CLOSER
DOOR STRIKE

APPROVED BY: _____

DATE: _____

VAULT STRUCTURES INC REVISIONS			
REV.	DESCRIPTION	DATE	APPROVED



Vault Structures, Inc.

3640 WORK DRIVE,
FORT MYERS, FL 33916,
Telephone: 239-332-3270
Fax: 239-332-5593

PROPRIETARY AND CONFIDENTIAL
THE INFORMATION CONTAINED IN
THIS DRAWING IS THE SOLE
PROPERTY OF VAULT STRUCTURES,
INC. ANY REPRODUCTION IN PART
OR AS A WHOLE WITHOUT THE
WRITTEN PERMISSION OF VAULT
STRUCTURES, INC IS PROHIBITED.

MATERIAL : _____
GAUGE : _____
GRAIN : _____
BEND RAD. : _____
K-FACTOR: _____

DWG. NO. VERTICAL TUBE DAY GATE-STD

TITLE:

DRAWN BY: SAC

MODEL BY: SAC

WEIGHT: 89.89

SCALE: 1:16

DATE: 11/19/2014

SHEET 1 OF 1

REV

X